This is the Liberty Street Complete Street presentation given at the Open House on November 20, 2013 at City Hall and at the Over-the Rhine Community Council Meeting on February 3, 2014 at the Rothenberg School. *Italicized* text represent the major talking points that went with each slide.





Liberty Street Complete Street Project




The Liberty Street Complete Street project will incorporate the "complete streets" transportation policy to the re-design of Liberty Street. This policy will balance the needs of all users so that the new roadway will allow safe, convenient and comfortable travel and access for pedestrians, bicyclists, Metro bus users, the Streetcar and the automobile. The project encompass the Liberty Street corridor from I-75 to I-71.




Phase I of the project will focus on the area between Central Parkway on the west to just east of Sycamore Street to the east. A different phase will address the east and west ends of the corridor. Phasing has been considered to make the project design more manageable.






Casino Neighborhoods **Working Group**



Over-The-Rhine **Community Council CPR 2012**

DOTE intends to develop several options to better integrate Liberty Street back into the fabric of Over the Rhine while retaining its necessary functionality. These context specific concepts will focus on improving pedestrian safety, comfort, and access along and across the street, investigating bicycle options through the corridor, improving roadway safety and aesthetics, and enhancing redevelopment opportunities.


Refinement of Alternatives/Development of Design Options
Review and Selection of Preferred Design Option
Includes cost estimates and identification of potential funding option



In April of 2013 City Council passed a motion directing the City's Department of Transportation and Engineering to initiate a study to "road diet" Liberty Street. Over the last few years, plans and forces brought the need for the Liberty Street Complete Street project to the forefront.

OVER-THE-RHINE







COMPREHENSIVE PLAN


JUNE 2002

The 2002 Over The Rhine Comprehensive Plan made recommendations for major improvements to OTR and Liberty Street.

The Brewery District Community Urban Redevelopment Corporation's

2011 BREWERY DISTRICT MASTER PLAN

A Strategy For Re-Populating Cincinnati's Brewery District
(Version 1.1)




BREWERY DISTRICT COMMUNITY URBAN REDEVELOPMENT CORPORATION plaserworks - Architecture & Urban Design

2011 BREWERY DISTRICT MASTER PLAN

The 2011 Brewery District Master Plan Asked for specific complete street type of improvements to Liberty Street

The last decade witnessed critical development south of Liberty Street. Revitalization translates into the numerous buildings renovated and booming economic activity. There is growing pressure to seize the opportunity to revitalize the northern half of OTR including ongoing improvements such as Findlay Market, Moerlein Brewery, Rookwood Pottery, etc. *Presently the width of Liberty* Street is seen as a barrier to connecting the north and south halves of OTR





The Over-The-Rhine Community Council applied for a Community Priority Request to the City in 2012 to study Liberty Street.

The Casino Neighborhood Working Group agreed to fund the Liberty Street Complete Street / road diet study. The Casino Neighborhood Working Group is comprised of representatives from five neighborhoods adjacent to the project area, the City's Department of Transportation and Engineering (DOTE), the City's Planning Department and OTR developers. They make recommendations as to the use of the OTR East TIF (tax increment financing) funds.

Over-The-Rhine Community Council CPR 2012

Casino Neighborhoods
Working Group

Design Process

LIBERTY STREET COMPLETE STREET PROJECT

Department of Transportation and Engineering, Transportation Planning and Urban Design

Design and Public Engagement Schedule

Phase I - Information gathering

- 1. Existing conditions survey:
 - a. Geometry roadway, driveways, alleys, radii, alignment
 - Traffic volumes and movement high turn locations (like Sycamore south to Liberty)
 - c. Accident history any problem locations, trends, possible solutions
 - d. Survey
- 2. Review of previous plans:
 - a. Brewery District Plan
 - b. Over the Rhine Plan
 - c. Design plans for Central Parkway and Liberty
 - d. Design plans for Liberty at Liberty Hill
 - Traffic impact analyses from development Casino, Brewery District, OTR redevelopment
 - f. Understanding of parking needs for residents, business and future business

Public Meetings / Internal Meetings

- a. Meet with Planning, ED and CD and other City agencies
- Public meeting with all stakeholders Residents, Community Councils, Institutions and Business Interests - "Are there any concerns with Liberty Street today?"

Phase II - Conceptual options

- 4. Development of Alternatives
 - No build no curb modifications except for bump-outs as part of a Streetscaping project
 - b. Minor modifications, similar to those in the OTR plan
 - c. Major modifications, similar to those in the Brewery District Plan
 - d. Others?
- 5. Public Meetings Present options for review and prioritizing
 - a. Meet with Planning, ED and CD and other City agencies
 - b. Present to City Council / Livable Communities, etc
 - c. Public meeting with all stakeholders Residents, Community Councils, Institutions and Business Interests - ""which of these alternatives should be pursued with further traffic analysis and in regards to viability?"

Phase III - Design

- 1. Development of Options
 - a. Option One
 - b. Option Two
 - c. Analysis
 - d. Traffic simulation model to prepare base condition
 - e. Potential geometric changes and lane changes for each alternative
 - f. Traffic analysis of alternative design concepts

- g. Cost estimate of alternatives
- Comparison matrix of issues economic redevelopment, pedestrian safety, bikes, trucks, other vehicular access, parking, cost

The end of Phase II will result in two options to pursue

Phase IV - Review options

- 2. Review of Alternatives
 - a. Review alternative data and issues
 - b. Modify as needed
 - c. Potential funding strategies
 - d. Phasing Options
- 3. Public Meetings Present options for review and to choose preferred design
 - a. Meet with Planning, ED and CD
 - b. Present to City Council / Livable Communities, etc
 - c. Public meeting with all stakeholders Residents, Community Councils, Institutions and Business Interests – "which of these alternatives should be pursued toward final construction documents?"
- Select preferred alternative
- 5. Research and identify funding options

The end of Phase IV will result in a final preliminary plan

Phase V - PS & E (Plans, Specifications and Estimate - the final design for bidding)


- 1. Construction Documents
- Review funding options
- Public Meetings Present final plans (or these can be half way thru the process if issues arise), phasing and funding options

The end of Phase V will result in a final plan that has been thoroughly vetted and ready for bidding and construction


NOTE: The DOTE / Transportation Planning and Urban Design Division will provide further funding to review and schematically plan the west end of Liberty Street, Central Parkway to Western Avenue, to assure complete connectivity with I-75 and I-71.


A five step process was envisioned to direct the project from planning & design to construction documents. Through the process, design options will be explored by the Department of Transportation and Engineering and presented to the public. A preferred option will then be presented to the City's Planning Department, Community Development, and to City Council. Final design plans will fold into construction documents ready for bidding and construction. While there are no funds available for construction immediately, DOTE will seek them during the construction document phase.


Historical Maps



On this view, the slides depict the evolution of the Liberty Street corridor and the City of Cincinnati from 1819 to the mid 80s.






















Liberty Street – "before". These photos taken by the City's Division of Engineering (precursor to the Department of Transportation and Engineering -DOTE), document the existing conditions two years prior to the actual Liberty Street widening project.

Looking East from Walnut St. (1955)



Looking East from Main St. (1955)



Looking East from Race St. (1955)





Looking East from Race St. (1957)

Looking East from Race St. (1958)

All demolition was to the south side of Liberty Street, the widening project left the north side businesses and institutions intact but resulted in a mostly haphazard group of un-usable properties on the south.





Looking East from Elm St. (1957)

Looking East from Elm St. (1958)

A "during demolition" and "after widening" set of pictures at Elm Street.



Looking SW from the NE Corner of Vine St. (1958)

Looking SW from the NE Corner of Vine St. (2013)


1958 to 2013 - 55 years later the widening did not heal by providing development opportunities along the south side of Liberty, consequently the remaining properties continue in a dilapidated stage.

Existing Surface Parking



Phase I of the Liberty Street Complete Street study includes information gathering of existing conditions. A survey was undertaken to accurately measure the roadway geometry, building placement and utility locations. DOTE is surveying existing parking options from adjacent surface parking lots to...

On Street Parking (144 Spots)




...on-street parking. Parking is obviously a major concern of all that live and work in Over-the-Rhine and will be a major talking point through this process.

Existing Transportation

Existing Metro bus routes have been mapped as well. DOTE has met with Metro to coordinate any of their potential changes and upgrades. Metro has no plans to utilize Liberty Street as a east — west connector but has added a Metro Plus route that will potentially be the precursor to a Bus Rapid Transit (BRT) route.

Green arrows show in-bound bus routes and red indicates out-bound routes. The purple lines on Elm Street and Race Street show the new Streetcar alignment.



Traffic Counts

A traffic engineering firm was hired to take counts of the existing traffic volumes and turning movements. These aid the project by allowing DOTE to design for these volumes for certain times of the day. The turning movements counts will also impact the design by indicating how many vehicles are turning at each intersection and how that impacts vehicular flow.

Further information to be gathered are accident history and Traffic Analysis from larger nearby developments such as the Horseshoe Casino, etc.



Developable Parcels



The Liberty Street Complete Street study will also measure how each option will impact the amount of developable land potentially available to the south. The 1957 widening left a number of properties on the south that were undevelopable due to their minimal size. Narrower roadway options will present more available land to the south that can be assembled into more buildable properties. These options will indicate how much roadway can be salvaged and assembled to make larger and better developable properties and potentially help restore the neighborhood fabric.



